

David Glinski has been in the building business since he founded and managed Tree House Woodworking Cooperative in 1972. Today he is president of Sunset Custom Homes Inc.; a successful custom home builder in Tucson, Arizona, incorporated since 1992.

usto

es,





THE VIEW-Near River Road and First Avenue, in an established neighborhood, this is what motivated my clients to purchase their lot.



The Homeowner met me on the lot prior to excavation. The existing house pad was built by a "wanna-be" contractor during the housing recession. The problem: He used soil with a high clay content, and it was three feet out of level. Existing soil conditions could not support a house. The solution: Over-excavate (remove) the clay, import new soil, and rebuild the house pad from the original natural grade and up. Price tag \$20,000.

An Engineered Pad

In 12" lifts, with the right amount of water, we achieved over 100% compaction in some areas!





The finished house pad is compacted to 95% or greater and is within 2" of being level. Great care was given to preserving and relocating the native vegetation.



Engineered Post Tension



Engineered Post Tension cables have #4 rebar, bent to the shape of a "hairpin", to support the **Live End** and **Dead End** of each cable.

Live End: Cables protrude through the form boards, for future tensioning.



Dead End: Embedded cable with "Hairpin" (#4 rebar concrete reinforcement).





The Slab is poured and Utilities are in.



Post tension cables were stressed to 33,000 lbs each. After inspection, the ends were cut and patched.



First Wall Up!



Jobsite is kept clean






We used the dining room as a makeshift office. The concrete block in the center is the Panic Room.





Many framing details such as this "barrel arch", were typical.
The indirect lighting that runs along length of the arch, was manufactured at Sunset Custom Homes' wood shop.





Roxul was used as a sound barrier in several interior walls.



"Smart House" wiring has many exciting applications. A hot water recirculation loop and pump were used with a high efficiency 75 gallon water heater to produce "Instant Hot" water at all faucets.

Two 3-ton Carrier "Performance Series" 16 SEER units were selected for heating and cooling.





Open-cell foam was used for insulation.



Architectural details were added throughout the home.





High efficiency skylights add light with less heat gain.





View from the rear patio





The final product!